

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-22,957-00-00

LEASE NAME I. Gottschalk

WELL NUMBER 1

SPOT LOCATION NE SW SE

SEC. 26 TWP. 13 SRGE. 18 ~~W~~ or (W)

COUNTY Ellis

Date Well Completed 5/82

Plugging Commenced 7/30/84

Plugging Completed 7/30/84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Reif Oil Operations, Inc.

ADDRESS P.O. Box 298, Hoisington, KS 67544

PHONE # (316) 653-7745 OPERATORS LICENSE NO. 5770

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6 - Hays, KS.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Arbuckle Depth to top 3618 bottom 3665 T.D. 3665

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/KC	water	3360	3581	8-5/8	250	none
Arbuckle	water	3618	3665	5-1/2	3664	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 4 bbl. cement, pressured up to 500# & held 15 sacks, shut-in & changed over to casing pump 12-3/4 bbl cement down casing @ 250#, pumped 15 sacks gel & 3 sacks hulls @ 400#, 1/2 sack hulls & water @ 250#, pumped 25 sacks cement @ 500#, pumped 3 sacks gel @ 500#, released plug, pumped 160 sacks cement @ 550#, pumped 1/2 bbl. water, shut well in. DV tool at 1290'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____
Address 1100 E. 8th - Hays, KS 67601

STATE OF Kansas COUNTY OF Barton, ss.

Tim Hertach (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


AUG 03 1984

(Signature) Tim Hertach

(Address) _____

CONSERVATION DIVISION
SUBSCRIBED AND SWORN TO before me this 31 day of July, 1984
Wichita, Kansas

My Commission expires: 3/11/87



Doris J. Denning
Notary Public