

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-00670-00-00  
**WELL PLUGGING RECORD**

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Ellis County, Sec. 31 Twp. 13 Rge. 18 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW

Lease Owner Anschutz Drilling Company, Inc.

Lease Name State Well No. 1

Office Address 612 Union National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-22 19 49

Application for plugging filed via telephone 12-22 19 49

Application for plugging approved via telephone 12-22 19 49

Plugging commenced 12-22 19 49

Plugging completed 12-22 19 49

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3785 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	206'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug at 207', put 15 sacks cement through drill pipe on bottom plug filled with heavy mud to 25'. Set top plug at 25', filled with cement to bottom of cellar

RECEIVED  
DEC 29 1949  
STATE CORPORATION COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.  
Address 612 Union National Bank Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
H. R. Jensen (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Jensen  
612 Union Nat'l Bk Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of December, 19 49

My commission expires September 12, 1953  
Notary Public.



**PLUGGING**  
FILE SEC 31 T 13 R 18  
BOOK PAGE 121 LINE 20

WELL LOG

ANSCHUTZ DRILLING COMPANY, INC.

State #1, SE SE NW 31-13-18  
Ellis County, Kansas

15-05100670-00-00

0	60	Clay & soil
60	85	Sand
85	207	Lime, shells & shale
207	540	Shale and shells
540	690	Sand
690	780	Shale
780	930	Sand
930	955	Shale
955	1270	Shale and shells
1270	1295	Shale and shells
1295	1350	Anhydrite
1350	1495	Shale and salt
1495	1790	Shale and salt
1790	1925	Shale and shells
1925	2005	Lime and shale
2005	2105	Lime and shale
2105	2285	Lime and shale
2285	2360	Lime and shale
2360	2385	Lime
2385	2390	Lime and shale
2390	2470	Lime and shale
2470	2660	Shale & lime shells
2660	2770	Shale and shells
2770	2885	Shale and shells
2885	2930	Shale and lime
2930	2985	Lime and shale
2985	3107	Lime and shale
3107	3115	Lime
3115	3185	Lime
3185	3240	Lime
3240	3314	Lime
3314	3356	Lime
3356	3416	Lime
3416	3460	Lime
3460	3500	Lime
3500	3548	Lime
3548	3598	Lime
3598	3643	Lime
3643	3650	Lime
3650	3678	Conglomerate
3678	3692	Conglomerate
3692	3745	Conglomerate
3745	3775	Arbuckle
3775	3785	Arbuckle
3785		Rotary Total Depth

COMMENCED: 12-11-49  
COMPLETED: 12-22-49

CASING RECORD

Set 8-5/8" surface casing at 206'  
with 125 sacks cement, cemented by  
Sun Cementing Co.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of  
the log of the #1 State located SE SE NW 31-13-18, Ellis County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

By: *H. R. Jensen*

this 28th day of December, 1949.

*Martha Boyer*  
Notary Public

**PLUGGING**

**FILE SEC 31-13-18**

**BOOK PAGE 121 LINE 20**

Subscribed and

My commission expires September 12, 1953