

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33810
Name: Walcher Oil, L.L.C
Address 1: 150 N. main, Ste 809
Address 2: _____
City: Wichita State: KS Zip: 67202 + _____
Contact Person: D.A. Walcher
Phone: (316) 267-1611
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet): _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 151-20124 500-01
Spot Description: _____
1108 990 NW SW SE Sec. 2 Twp. 27 S. R. 13 East West
2246 2310 Feet from North / South Line of Section
Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner: Per Gas 4/03/10
 NE NW SE SW
County: Pratt
Lease Name: S&S Unit Well #: 1
Date Well Completed: 7-23-05
The plugging proposal was approved on: 11/2/10 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 11/3/10
Plugging Completed: 11/8/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Setting Cost
		Surface	8 5/8"	421	375 350 Sacks Cement (from ACO-1)
		Production	5 1/2"	449 ³	N/A

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Blew gas off well & well blew out. Shut well in. Pumped 30 sacks cement down tubing, displaced to 3650'. Tagged cement in tubing at 2735'. Shot tubing off at 2708' & pumped 30 sacks cement, displaced to 2708'. Shut in, check well was dead. Pulled tubing out & did bond log. Perforated 5 1/2" casing. Ran tubing to 800' & pumped 80 sacks cement, circulated cement & pulled tubing out. Hooked up to 5 1/2" casing & pumped 220 sacks cement. Ran tubing to 500' & pumped 50 sacks cement. Pulled tubing out & swedge in. Pumped 10 sacks cement, pressured up to 250#. Pumped 5 sacks cement down 8 5/8" casing at 1200 psi. Cut surface & casing off 4' below ground.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc. (Richard McIntyre)
Address 1: 190 US ⁵⁶ Highway Address 2: _____
City: Ellinwood State: KS Zip: 67526
Phone: (620) 727-3410

Name of Party Responsible for Plugging Fees: Walcher Oil, LLC
State of Kansas County, Pratt, ss. Richard McIntyre (agent) & Steve Pfeifer (Inspector) Representatives Operator on above-described well,
(Print Name)

I, the undersigned, being first duly sworn, depose and say that I have knowledge of the facts statements, and matters herein contained, and the contents of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: D. Walcher for Richard McIntyre & Steve Pfeifer, 1/9/2011

RECEIVED
JAN 10 2011
KCC WICHITA