


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

1505120696-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County. Sec. 28 Twp. 13 Rge. 19 (E) (W)
Location as "NE/CNW%SW%" or footage from lines NE SW SE
Lease Owner Landes Exploration Co.
Lease Name Bemis Well No. 1
Office Address 416 Union Center Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 25 19 70
Application for plugging filed November 25 19 70
Application for plugging approved November 25 19 70
Plugging commenced November 25 19 70
Plugging completed November 25 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3502 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	219'	8 5/8"	219'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Plug: 550'/70 sacks cement
210'/20 sacks cement
40'/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 - 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
D. L. Hellar, President of Hellar Drlg. Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar D. L. Hellar, President
339 Union Center Bldg., Wichita, Kansas 67202
(Address)



Subscribed and sworn to before me this 1st day of December, 19 70
My commission expires March 25, 1972
Catherine Darcey
Notary Public.

DRILLER'S LOG

COMPANY: Landes Exploration Co., 416 Union Center Bldg., Wichita, Kansas 67202
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202
 LEASE: #1 Bemis
 LOCATION: NE SW SE 28-13-19, Ellis County, Kansas
 COMMENCED: November 20, 1970
 COMPLETED: November 25, 1970
 CASING: Set 8 5/8" Surface Casing @ 219'/150 sacks cement

0-80	Clay & Rock
80-219	Shale
219-635	Shale-Red Bed-Sand
635-1450	Shale, Sand-Red Bed
1450-1507	Red Bed & Shale
1507-1552	Anhydrite
1552-1800	Red Bed & Shale
1800-2090	Shale
2090-2250	Shale & Lime
2250-2372	Shale
2372-2445	Lime & Shale (Ft. Riley)
2445-2605	Lime & Shale
2605-2830	Shale & Lime
2830-2990	Lime & Shale
2990-3315	Shale & Lime
3315-3430	Lime & Shale
3430-3502	Lime
3502	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 2 - 1970
 CONSERVATION DIVISION
 Wichita, Kansas

D & A

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Bemis, located in NE SW SE 28-13-19, Ellis County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 1st day of December, 1970.

CATHERINE DANCEY
 NOTARY PUBLIC
 SEDGWICK COUNTY, KANSAS
 My Commission Expires
 March 25, 1972.

Catherine Dancey
 Notary Public - Catherine Dancey