

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME R. V. Nelson

WELL NUMBER 1

1787 Ft. from S Section Line

4813 Ft. from E Section Line

SEC. 24 TWP. 34S RGE. 11W(E) or (W)

COUNTY Barber

Date Well Completed 5-18-84

Plugging Commenced 12-16-92

Plugging Completed 12-21-92

LEASE OPERATOR C. E. Kimmell

ADDRESS 1716 Milam Bldg., San Antonio, Texas 78205

PHONE# (210) 223-4452 OPERATORS LICENSE NO. 09459

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-3-92 (date)

by Dwane Rankin

(KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Stalnaker Depth to Top 3948 Bottom 4050 T.D. 5360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surf.	315	8 5/8	315	0
		Surf.	5368	4 1/2	5368	2945

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Dump sand and fill to 3900', Dump 5 sx cmt. on top, cut csg. at 2945'. 300# Hulls. 10 sx gel
50 sx cmt, 10 sx gel, 100# Hulls. 8 5/8 wiper plug, 100 sx cmt, 60/40 Poz with 6% gel.

Name of Plugging Contractor Hardtner Well Service

RECEIVED
STATE CONSERVATION COMMISSION
MAR 1 1993
CONSERVATION DIVISION
Wichita, Kansas

Address P. O. Box 245, Hardtner, Ks. 67057

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: C. E. Kimmell

STATE OF Texas COUNTY OF Bexar, ss.

C. E. Kimmell

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 1716 Milam Bldg., San Antonio, TX 78205

GENEVIEVE S. THOMASON
Notary Public, State of Texas
My Comm. Exp. 04-30-93



SUBSCRIBED AND SWORN TO before me this 26th day of February, 1993

Genevieve S. Thomason
Notary Public

My Commission Expires: 4-30-93

USE ONLY ONE SIDE OF EACH FORM

15-007-21791-0001



MICRO-SEISMOGRAM[®] LOG-CASED HOLE

Thank you!!

COMPANY C E KIMMELL

WELL # 1 NELSON

FIELD N. KIOWA

COUNTY BARBER STATE KANSAS

Location 1787' FSL 467' FWL
OF SW-NW-SW

Other Services:

Sec. 21 Twp. 34S Rge. 11W

Permanent Datum GROUND LEVEL Elev. 1349'

Elev.: KB 1358'

Log Measured From KB 9 Ft. Above Perm. Datum

D.F.

Drilling Measured From KB

G.L. 1349'

Run No.	<u>ONE</u>
Date & Time Survey	<u>19 MAY 84</u>
Date & Time Cementing	<u>16 MAY 84</u>
Type Cementing Operation	<u>PRIMARY</u>
Depth Driller	<u>5360'</u>
Depth Welex	<u>5320'</u>
Logged Interval	<u>53.14'</u> to <u>2700'</u>
Casing Driller	<u>4 1/2"</u> to <u>TD</u>
Fluid Column - D.V. Foot	<u>N/A</u>
Squeeze Depth	<u>N/A</u>
Amount & Type Cement	<u>N/A</u>
Amount & Type Admix	<u>N/A</u>
Type Fluid in Hole	<u>WATER</u>
Fluid Level	<u>FULL</u>
Salinity PPM Cl	<u>N/A</u>
Weight lb/gal - Vis.	<u>N/A</u>
Approx. Logged Cem. Top	<u>2945'</u>
Calculated Cement Top	<u>N/A</u>
Max. Hole Temperature	<u>131</u>
Tool No.	<u>61376</u>
Spacing Recorded	<u>4 FT</u>
Equipment - Location	<u>1891 PRATT</u>
Recorded by	<u>C. HOWERTON</u>
Witnessed by	<u>MR. JANNY</u>

GULF HOLDING PRINT

RECEIVED
STATE CONSERVATION COMMISSION
OCT 10 1992
CONSERVATION DIVISION
MINNIE BARNER

Fold Here