


15-171-00020-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Scott County, Sec. 32 Twp. 18S Rge. (E) 31 (W)
Location as "NE/CNW%SW%" or footage from lines. C SW SW
Lease Owner Pickrell Drilling Company
Lease Name Christy "A" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 9 19 61
Application for plugging filed June 9 19 61
Application for plugging approved June 9 19 61
Plugging commenced June 9 19 61
Plugging completed June 9 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker, Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4666' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 270'. Set Plug, Cemented with 25 sacks cement. Heavy mud to 40'. Set Plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1961
06-16-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Gerald W. Pike (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald W. Pike
Gerald W. Pike, Partner
705 Fourth National Bank Bldg., Wichita, Ks

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1961

My commission expires September 24, 1962
Maxine Johnson
Maxine Johnson Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita 2, Kansas

Rotary Drilling Commenced 5/26/61

Rotary Drilling Completed 6/9/61

LOCATION: CHRISTY A #1 - C SW. SW, Sec. 32-18S-31W
Scott County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 276' (6 jts.) 8 5/8" 20# Surface Casing with 175 sacks cement.
Circulated. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>	
60'	Sandy Surface Soil	4011'	
140'	Sand & Post Rock	4065'	
510'	Blue Shale	4075'	
670'	Grey Shale	4380'	
880'	Black Shale & Sand	4580'	
1070'	Shale & Shells	4595'	
1420'	Shale & Sand	4646'	
1480'	Blue Shale	4666'	
1760'	Red Bed & Shale		
1785'	Shale & Shells	<u>Slope Test</u>	
2170'	Red Bed & Shale	1760'	0°
2280'	Red Bed, Shale & Shells	2765'	0°
2310'	Anhydrite	3448'	0°
2540'	Red Beds, Shale & Shells	4305'	0°
3086'	Lime & Shale		
3335'	Lime	<u>S. L. M.</u>	
3675'	Lime & Shale	2170'	
3743'	Lime, Shale & Sand	3675'	
4011'	Lime & Shale	4595'	
4065'	Lime		
4140'	Lime & Shale		
4540'	Lime		
4666 ^{ft}	Lime & Chert T.D.		

RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1961
06-16-61
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Gerald W. Pike, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By Gerald W. Pike
Attorney-in-Fact
Gerald W. Pike

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 14th day of June, 1961, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared Gerald W. Pike, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
Notary Public