

KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 14 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Range Oil Company

Complete Address 402 Insurance Bldg., Wichita, Kansas

Lease Name Sophia Dreiling Well No. 1

Location NW SW NE Sec. 11 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3800'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor L, J. Dreiling

Address Victoria, Kansas License No.       

Operation Completed: Hour 5:45 A Day 12 Month 7 Year 1970

The above well was plugged as follows:

RTD 3800' 8 5/8 csg set at 181' cwc Cmt. Mat. 100 sk reg poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/14/70  
INV. NO. 2229-U

Signed: Leo J. Massey  
Well Plugging Supervisor