

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 106-64
LOCATION NE SE NE
SEC. 21 TWP. 11 RGE. 17 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Bemis

Operator Phillips Pet Co Address Box 779 Great Bend, Kans

Field _____ County Ellis

Total Depth 3412 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

15" at 205' circulated with cement - 12 1/2" at 1094' circulated with
400 sax cement - 7" at 3008' with 225 sax cement behind - P.B. to
3056', perforated at 3988'.

Filled with sand to 2970', set 5 sax cement with dump bailer - pulled
2400' 7" - filled hole with commercial mud to 300' (34 sax Gel) -
set rock bridge and 300' with 30 sax cement - mud to 25', set
rock and 15 sax cement to bottom cellar.

Edwin Perry
District Conservation Agent

RECEIVED
PLUGGING STATE CORPORATION COMMISSION
FILE SEC 21 T. 11 R. 17W
BOOK PAGE 106 LINE 64
OCT 29 1956
CONSERVATION DIVISION
Wichita, Kansas

Date 10-27-56