

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NE

SEC. 21 TWP. 11 RGE. 17W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease F.A. Bemis

Operator Phillips Pet Co Address Box 779 Great Bend, Kans

Field _____ County Ellis

Total Depth 3461 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

20" at 162' circulated with cement - 12 $\frac{1}{2}$ " at 1132' circulated
with 750 sax cement - 8 5/8" at 3435' with 250 sax cement behind.
Filled with sand to 3420', set 6 sax cement with dump bailer,
pulled 2225' 8 5/8" - filled hole with mud to 400' (60 sax gel),
set rock bridge and 40 sax cement at 400' - mud to 25', set rock
and 20 sax cement to bottom cellar.

District Conservation Agent

Date 11-4-56

PLUGGING
FILE SEC 21 T 11 R 17W
BOOK PAGE 106 LINE 63

RECEIVED
CONSERVATION
11-09-56