

15-051-06225-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

Date  
8-7-50 File  
10-17-52 File

7-10-  
52-41 take your pick  
FILE NO.

330' from N and 1000' LOCATION Noth line  
Approx SW NW SW  
SEC. 22 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Bemis

Operator British American Address Tulsa, Okla

Field Bemis County Ellis

Total Depth 3475 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 1161' circulated with 500 sax cement - 7" at  
3434 with 1/5 sax cement behind.

String cable tools lost in bottom - filled with chat to  
3425', set 5 sax cement with dump bailer, pulled 2500' 7",  
filled with mud to 300', set rock and 25 sax cement, mud to  
30', set rock and 10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 22 T 11 R 17  
BOOK PAGE 52 LINE 11

STATE CORPORATION COMMISSION  
NOV - 6 1952  
CONSERVATION DIVISION  
Wichita, Kansas

*Edmund P. ...*  
District Conservation Agent  
Date 11-4-52