

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: NE NW SE Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3438

I have this date completed supervision of plugging of:

Lease Name: J. Johansen Oil Well No. 15

Operator's Full Name: Socony - Mobile Oil Co

Complete Address: 300 N. Broadway Wichita, Kansas

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6PM Day 19 Month 11 Year 60

The above well was plugged as follows:

10 3/4" 1185' circulated with 500 sax cement - 7" 3433' with 200 sax cement.  
PB to 2906' - perforated 2886'.

Filled with sand to 2870', set 4 sax cement with dump bailer, pulled 2447'  
7" to 500', circulated hole with heavy mud through 7" at 500' ( 40 sax cel),  
displaced 30 sax cement through 7" at 500', heavy mud to 170', displaced  
30 sax cement through 7" at 170', heavy mud to 35', set bridge and 10 sax  
cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

INVOICED RECEIVED  
DATE 11/30/60  
INV. NO. 2279-11  
NOV 23 1960  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: