

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1965  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Frank J Black

Complete Address: Box 150 Mc Pherson Kansas

Lease Name J Johanson Well No. 11

Location NE c SE Sec. 22 Twp. 11 Rge. 17 (E) (W)

County Ellis Total Depth 3396

Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Lynch Casing Pulling

Address: Rt 4 Great Bend Kansas License No. 457

Operation Completed: Hour 50M Day 8 Month Nov Year 1965

The Above well was plugged as follows:

Total Depth-3396 16" set at 58' 10 3/4 setat 1130 7" set at 3392 cw 200 sc

Sand to 3380 and 4 sax cement dumped with dump bailer. Shot and pulled pipe to 500'

and circulated 18 sax jell mud, pulled pipe to 450' and displaced 30 sax cement, pulled

pipe to 200' and displaced 20 sax cement, pulled pipe out of hole, built bridge at

40' and topped with 10 sax cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Delbert P. Liker  
Well Plugging Supervisor

INVOICED

DATE 11/12/65

INV. NO. 2162-4