

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150 Mc Pherson, Kans

Lease Name J. Johansen ~~Sub~~ Well No. 9

Location SW NE 1/4 Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3418

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Lynch

Address: Great Bend, Kans License No. 457

Operation Completed: Hour 6PM Day 10 13 Month 10 Year 65

The Above well was plugged as follows:

15" 56' circulated - 10 3/4" 1158' circulated with cement - 7" 3418'
with 200 sax cement.

Sanded back to 3400', set 5 sax cement with dump bailer - pulled 2732'
7" to 300' circulated hole with heavy gel mudthrough 7" - pulled pipe
to 450', displaced 25 sax cement through 7" - heavy mud to 200',
displaced 25 sax cement through 7" at 200', heavy mud to 30', set bridge
and 10 sax cement to bottom cellar,

Mudding and cementing by Lynch Pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/20/65

INV. NO. 2004-W