

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-051-05819-000

RECEIVED

NOV 2 1965
11-02-65

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Frank J Black
Complete Address: Box 150 McPherson
Lease Name J. Johanson DNB VCC Well No. 7
Location Sec. 22 Twp. 11 Rge. 17 (E) (W)
County Ellis Total Depth 3402
Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____
Plugging Contractor: Lynch Casing Pulling
Address: Rt 4 Great Bend Kans. License No. 457
Operation Completed: Hour 4PM Day 23 Month Oct Year 1965

The Above well was plugged as follows:

TD-3402-16 "at 54' - 10" at 1158' - 7" at 3396'
Lower back to 3380 and displaced 4 sac cement. Shot
8 7" pipe and pulled same to 500' and circulated 18
sac mud, pulled pipe to 450' and displaced 30 sac
cement, pulled same to 200' and displaced 30 sac cement
pulled pipe out of hole and capped well 10 sac cement

Orders given by Elden Pitz and reported by G. L. Liker

I hereby certify that the above well was plugged as herein stated

INVOICED

Signed: Gellus P. Liker
Well Plugging Supervisor

DATE 11/2/65
INV. NO. 2081-W