

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: NW SW NE Sec. 22 Twp. 11 Rge. 17 (E) (W)  
Name of Field: \_\_\_\_\_ Total Depth: 3465

I have this date completed supervision of plugging of:

Lease Name: J. Johansen AUB rcc Well No. 4  
Operator's Full Name: Socony Mobile Oil Co  
Complete Address: 300 N Broadway Wichita, Kans  
Plugging Contractor: Ace Pipe Pulling Co  
Address: Great Bend, Kansas License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 11 Month 11 Year 60

The above well was plugged as follows:

16" 42' - 10 3/4" 1189' circulated with cement - 7" 3459' with 200 sax cement  
Filled with sand to 3440', set 4 sax cement with dump bailer, pulled  
2441' 7" to 500', circulated hole with heavy mud through 7" at 500',  
( 31 sax Gel), displaced 30 sax cement through 7" at 500', heavy mud  
to 180', displaced 30 sax cement through 10 3/4" at 180', heavy mud to  
35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

NOV 23 11-16-60  
DATE 11/23/60  
INV. NO. 2221-W