

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: SW SW NE Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3432

I have this date completed supervision of plugging of:

Lease Name: J. Johansen ANBYCC Well No. 5

Operator's Full Name: Socony Mobile Oil Co

Complete Address: 300 N Broadway Wichita, Kansas

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 7 Month 11 Year 60

The above well was plugged as follows:

16" 55' - 10 3/4" 1175' with 528 sax cement - 7" 3432 with 200 sax cement -

PB to 3428' - perforated at 3402'.

Filled with sand to 3380', set 4 sax cement with dump bailer, pulled 2346' 7"

to 450', circulated hole with heavy mud through 7" at 450', (27 sax Gel),

displaced 30 sax cement through 7" at 450', heavy mud to 160', displaced

30 sax cement through 7" at 160', heavy mud to 35', set bridge and 10 sax

cement to bottom collar.

Mudding and cementing by Halliburton Co.

Signed: *E. L. Petty*
Conservation Division Agent

Reviewed: *J. Lewis*
Field Supervisor

Remarks:

11-16-60
INVOICED
DATE 11/23/60
INV. NO. 2330-W