

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

04-05-61

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: NW SW SE Sec. 22 Twp. 11 Rge. 17 (E) (W) \_\_\_\_\_  
Name of Field: \_\_\_\_\_ Total Depth: 3428

I have this date completed supervision of plugging of:

Lease Name: Johannsen Well No. 2

Operator's Full Name: Sohio Oil Co

Complete Address: Box 673 Russell, Kansas

Plugging Contractor: Knight Casing Pulling Co

Address: Ellinwood, Kansas License No. 456

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3PM Day 30 Month 3 Year 61

The above well was plugged as follows:

10 3/4" 1171' circulated with cement - 7" 3427' with 150 sax cement.  
Filled with sand to 3415', set 5 sax cement with dump bailer, pulled  
2480' 7" casing - filled hole with heavy gel mud to 400', set 20 sax  
cement at 400', heavy gel mud to 160', set 20 sax cement at 160',  
heavy gel mud to 50', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Co pump truck.

Signed: *Edon Petty*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

INVOICED  
DATE 4/14/61  
INV. NO. 2910-W