

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis
Location: NW HW SE Sec. 22 Twp. 11 Rge. 17 (E) (W) _____
Name of Field: _____ Total Depth: 5418

I have this date completed supervision of plugging of:

Lease Name: J. Johansen DUG YCC Well No. 2
Operator's Full Name: Socony Mobil Oil Co
Complete Address: 300 N Broadway Wichita, Kans
Plugging Contractor: Ace Pipe Pulling Co
Address: Great Bond, Kans License No. 2
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 4 Month 11 Year 60

The above well was plugged as follows:

10 3/4" 1155' circulated with 528 sax cement - 7" 3403' with 200 sax cement.
Filled with sand to 3390', set 4 sax cement with dump bailer, pulled 1993' 7"
to 460', circulated hole with heavy mud through 7" (32 sax Col), displaced
30 sax cement through 7" at 460', heavy mud to 160', displaced 30 sax
cement through 7" at 160', heavy mud to 35', set bridge and 10 sax cement
to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: Edna Perry
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

RWD
INVOICED 11-10-60
DATE 11/23/60
INV. NO. 2722-11