

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 17-7

LOCATION SE NE NE

SEC. 22 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 8-A Lease Johansen

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 3412 Feet.

Plugging Contractor C.E.Shull

Plugging Contractor's License No. 8

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

15" at 119' circulated with cement - 10 3/4" at 1090' circulated  
with 525 sax cement - 7" at 3367' with 255 sax cement behind.  
Filled with sand to 3320', set 5 sax cement with dump bailer,  
pulled 2480' 7" - mudded to 300', set rock and 25 sax cement,  
mudded to 35' set rock and 10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 22 T 11 R 17  
BOOK PAGE 17 LINE 2

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 18 1954  
03-18-54  
CONSERVATION DIVISION  
Wichita, Kansas

*Edwin Petty*  
District Conservation Agent  
3-15-54  
Date \_\_\_\_\_