

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 17-8
LOCATION NW NW NE
SEC. 22 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1-X Lease Johansen A ANG KC

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 5491 Feet.

Plugging Contractor C. E. Shull

Plugging Contractor's License No. 8

Address _____

(Describe briefly the manner in which the well was plugged)

15" at 106' circulated with cement - 10 3/4" at 1086' circulated
with 400 sax cement - 7" at 3484' with 200 sax cement behind.
Sand to 3475', set 3 sax cement with dump bailer, pulled 2320'
7" - filled with mud to 300', set rock and 25 sax cement, mud
to 30', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 22 T 11 R 17W
BOOK PAGE 17 LINE 8

REC'D
03-29-54

E. J. Petty
District Conservation Agent

Date 3-21-54