

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

NOV 18 1960
11-18-60
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: NE SW NE Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3474 3489 AWB
KCC

I have this date completed supervision of plugging of:

Lease Name: J. Johansen AWB KCC Well No. 5

Operator's Full Name: Socony Mobile Oil

Complete Address: 300 N Broadway Wichita, Kansas

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 15 Month 11 Year 60

The above well was plugged as follows:

10 3/4" 1174' circulated with 525 Sax cement - 7" 3436' with 200 sax cement.
Filled with sand to 3425', set 4 sax cement with dump bailer, pulled 2432'
7" to 500' circulated hole with heavy mud through 7" at 500' (40 sax Gel),
displaced 30 sax cement through 7" at 500', heavy mud to 170', displaced
30 sax cement through 7" at 170', heavy mud to 35', set rock bridge and
10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 11/23/60
INV. NO. 2223-11