

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 0-0 County: Ellis

Location: SW SW SE Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 5450

I have this date completed supervision of plugging of:

Lease Name: Johansen Well No. 1

Operator's Full Name: Sohio Oil Co

Complete Address: Box 675 Russell, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 25 Month 1 Year 59

The above well was plugged as follows:

10" at 40' - 10 3/4" 1210' circulated with cement - 7" 5454'
with 150 sax cement behind.

Pulled 2555' 7" to 500', circulated hole with heavy mud through
7" (20 sax Gel), displaced 50 sax cement through 7" at
400', heavy mud to 180', displaced 50 sax cement through 7",
heavy mud to 50', set rock and 10 sax cement to bottom collar.

Mudding and cementing b West Supply Co's pump truck.

Signed: Edon Letty
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 22 T. 11 R. 17W
BOOK PAGE 6 LINE 5

RECEIVED
JAN 29 1959
CONSERVATION DIVISION
Wichita, Kansas