

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

R

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 14-38 County: Ellis

Location: SE NE SW Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 5481

I have this date completed supervision of plugging of:

Lease Name: Bemis Well No. C-7

Operator's Full Name: Sohio Oil Co

Complete Address: Box 676 Russell, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_ No \_\_\_

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 3 Month 3 Year 59

The above well was plugged as follows:

1 1/2" at 52' - 10 3/4" 1218' circulated with cement - 7" 3474' with 150 sax cement behind.

Filled with sand to 5400', set 5 sax cement with dump bailer, pulled 2000'

7" to 755' circulated hole with heavy mud through 7" ( 50 sax Gel ),

displaced 50 sax cement through 7" at 735', heavy mud to 555', displaced

30 sax cement through 7" at 555', heavy mud to 30', set rock and 10 sax

cement to bottom cellar.

Mudding and cementing by West Supply Co's pump truck.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC 22 T. 11 R. 17W  
BOOK PAGE 14 LINE 38

03-07-59