

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40072-00-00
Spot: SWNESE Sec/Twnshp/Rge: 4-29S-4E
1518 feet from S Section Line, 993 feet from E Section Line
Lease Name: MCCLURE EAST Well #: X2 (Per Ab Well Database)
County: BUTLER Total Vertical Depth: 1550 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	225	4		320 SXS

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2009 8:00 AM
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 938-2388

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2009 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

MOVED IN RIGGED UP QUALITY WELL SERVICE STARTED IN HOLE W/WORKSTRING CIRCULATING AND DRILLING HOLE @ 1550', WITH TBG @ 1520, QUALITY WELL SERVICE MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL AND DISPLACED IN CASING. RIH W/4-1/2" CASING @ 225', ORANGE PEELED 4-1/2" TO 8-5/8". RIH W/TBG @ 270', CIRCULATED CEMENT TO SURFACE, SWEDGED INTO 4-1/2" CASING, QUALITY WELL SERVICE MIXED & PUMPED 320 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1:00 PM 12-17-2009. QUALITY WELL SERVICE CEMENT TICKET # 3984.

RECEIVED
FEB 22 2010

Remarks: CONTROL NUMBER / 20090044-00 X2 (Per Ab Well Database) KCC WICHITA

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)