

"CORRECTED"

Als. inv'd.
#2011060256
9/14/09
8 (26.26)

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03114-00-01
Spot: SENWNWNE Sec/Twnshp/Rge: 30-9S-22W
4638 feet from S Section Line, 2088 feet from E Section Line
Lease Name: FARRELL A Well #: 1W
County: GRAHAM Total Vertical Depth: 3885 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2255 S WADSWORTH, STE 205
LAKEWOOD, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	189	0	w/unknown sxs cmt
L1	3.5	3787	0	w/190 sxs cmt
PROD	4.5	3885	0	w/unknown sxs cmt

Well Type: EOR UIC Docket No: E22217.1 Date/Time to Plug: 06/28/2010 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN CURLEY Company: VENTURE RESOURCES, INC. Phone: (785) 731-5073

Proposed Plugging Method: Ordered 260 sxs 60/40 pozmix - 4% gel - 600# hulls.
Perf 1222' w/197 sxs.
3 1/2" liner set at 3787' w/190 sxs cement.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2010 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Tied onto 3 1/2" - pumped 190 sxs cement with 600# hulls.
S.I.P. 500#.
Tied onto backside - pumped 110 sxs cement - no pressure - ordered more cement.
Tied back on the backside - pumped 50 sxs cement.
S.I.P. 50#.

RECEIVED
JUL 08 2010
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #17669.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

CM

~~IMPERIAL OIL CO~~ #1 FARRELL 30-9-22W
 C NW NE
 Contr. IMPERIAL OIL GRAHAM County
 E 2387 RB Comm. Comp. 2-9-62 IP 91 BOPD/LANS

Tops	Depth	Datum
ANH	1927	+460
HEEB	3619	-1232
TOR	3640	-1253
LANS	3654	-1267
TD	3885	-1498

Casing
 8" 189
 4" 3885
 DST 3648-77/2 HRS, 360' W, BHP 1175#
 DST 3774-3805/2 HRS, 1125' W, BHP 1120#
 DST 3803-19/30", 15' SL OCM, BHP 60#
 DST 3835-58/30", 10' M, BHP 935#
 PERF 20/3811-16: ACTD 1750: SWB @ RATE
 OF 180 BOPD

RED LINE NW POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS