

4-050314

8-21

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-23,169-00-00

NW SE SW \_\_\_\_\_/4 SEC. 13, 13 S, 18 W  
990 \_\_\_\_\_ feet from S section line  
3630 \_\_\_\_\_ feet from E section line

Operator license# 9394

Lease: Polifka Well # B-1

Operator: D-Oil, Inc.

County: Ellis 122.27

Address: P.O. Box 278  
Victoria, Kansas 67671  
785-735-9225

Well total depth 3762 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 167 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing Company License# -

Address: \_\_\_\_\_

Company to plug at: Hour: A.M. Day: 21 Month: August Year: 1998

Plugging proposal received from: Alfred Dreiling

Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Order 190 sxs 60/40 pozmix - 10% gel - 500# hulls - 20 sxs gel.  
8 5/8" at 167' w/125 sxs. 5 1/2" at 3762' w/150 sxs. (Two staged 1430' to surface)  
Perfs at 3500' - 3518'; 3546' - 3550'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour 10:30 A.M. Day: 21, Month: August, Year: 1998

Actual plugging report:

- 1) Tied onto 5 1/2" casing - pumped and squeezed with 40 sxs cement and 150# hulls.
- 2) Pumped 20 sxs gel and 350# hulls.
- 3) Pumped and squeezed with 125 sxs cement. Max. P.S.I. 1000#. S.I.P. 500#.
- 4) Backside cement visible at surface.

Remarks:

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: 2175 GL

I did [ X ] / did not [ ] observe the plugging.

Martin Miller  
(agent)

Form CP-2/3

INVOICED

DATE SEP 01 1998

INV. NO. 51230