

4-032139

TC:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

3-7

API Number: 15-051-06164-0000

SE SW SW /4 SEC. 21, 11, 17 W
330 feet from S section line
4290 feet from E section line

Operator license# 6273

Lease: Bemis Well # A-1

Operator: Robert R. Price Operations, Inc.

County: Ellis

Address: P.O. Box 470442
Tulsa, OK 71417

Well total depth 3473 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 1197

feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Chase Well Service, Inc. License# 6123

Address: Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 7 Month: March Year: 1996

Plugging proposal received from: Robert Price & District #4 Staff

Company: Robert R. Price Operations, Inc. Phone:

Were: Order 550 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Work string tubing.

03-27-96

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 1:15 P.M., Day: 7, Month: March, Year: 1996

Actual plugging report: 10 3/4" set at 1179' cwc with 450 sxs. 7" set at 3468' with 100sxs cwc. 3 1/2" tubing with packer set at 3200' for cement squeeze caused packer and tubing to be cemented in from 3200' to 2000'. Tubing was ran into 2310'. Spotted 115 sxs cement blend. Pulled tubing to 1310' - circulated with 145 sxs cement blend. Pulled tubing topped off with 20 sxs cement blend. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

Form CP-2/3

3-28-96

45161

3-7 MAY 17 1996