

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 7744

Operator: Sho-Bar Energy, Inc.

Name & Address P.O. Box 217

Harper, KS 67058

API NUMBER 15-119-01,000-00-01

NE NW SE, SEC. 30, T 34 S, R 26 W/E

2310 feet from S section line

1650 feet from E section line

Lease Name Fincham Well # 2-30

County Meade 211.86

Well Total Depth 6519 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1445

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Service Company License Number _____

Address Liberal, KS

Company to plug at: Hour: 4 p.m. Day: 1 Month: 3 Year: 1991

Plugging proposal received from Allen Barby

(company name) Sho-Bar Energy, Inc. (phone) 405-921-3366

were: 4 1/2" at 6514' w/310 sx cement, Perfs at 5483-87'

1st plug pump 1 sx hulls and 25 sx cement and 4 1/2" wiper plug,

2nd plug pump 50 sx cement at 1450',

3rd plug pump 30 sx cement at 600',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None _____ X

Operations Completed: Hour: 6:30 p.m. Day: 1 Month: 3 Year: 1991

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement and 4 1/2" plug,
Circulate hole with mud and spotted through 4 1/2" casing:

2nd plug pumped 50 sx cement at 1450',

3rd plug pumped 30 sx cement at 602',

4th plug pumped 10 sx cement at 40-0'.

MAR - 5 1991

Remarks: Used common cement by Halliburton. Recovered 2373' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.

DATE: 3-15-91

CONTRACT NO. 31196 MAY 03 1991

Signed Steve Durrant
(TECHNICIAN)