

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-21269-0000

SE, Sec. 22, T 11 S, R 17 WE

330 feet from N(S) section line

495 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6854

Lease Name Johansen Well # 9

Operator: Sohio Petroleum Co.
Name &
Address P.O. Box 30, Casper, Wyo. 82602

County Ellis

Well Total Depth 3402 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4" feet 309'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number 5287

Address 1100 E. 8th, Hays, Ks. 67601

Company to plug at: Hour: 2:00 PM Day: 11 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Rudy Herman

(company name) Sohio Petroleum Co. (phone) 913-637-5290

were: Order out 215 sacks 50 posmix - 4% Gel. - 3% Gel. G., 28 sacks Gel., 5 sacks shells & 7" plug.

Signed *[Signature]*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00 PM Day: 11 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 10 3/4" - 309' SP. W/ 225 sacks cement, 7" set at 3401' W/ 100 sacks cement, D.V. tool at 1163' W/ 300 sacks cement to surface. Top perf. 3387'. Ordered 215 sacks 50 posmix - 4% Gel. - 3% Gel. G., 28 sacks Gel., 5 sacks shells & 7" plug. Pumped in 7", 25 sacks cement, 4 sacks shells, 23 sacks Gel., 70 sacks cement, 5 Gel., 1 sack shells, released plug & followed W/ 70 sacks cement. Maximum pressure 700 pounds.

Remarks: 10 3/4" S.P. cement to surface.

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1982
10-19-82

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did) (did not) observe this plugging.

Signed *[Signature]*
(TECHNICIAN)

10-25-82
1458-W