

4-061026

12-16

05811-0000  
1937

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051  
NE NW NE /4 SEC. 22, 11 S, 17 W  
4950 feet from S section line  
1650 feet from E section line

Operator license# 8925

Lease Johansen Well # A-2

Operator: Liberty Operations & Completions  
Inc.

County: Ellis

Address: 308 W. Mill  
Plainville, Kansas 67663

Well total depth 3449 <sup>112.09</sup> feet  
Conductor Pipe: 16 inch @ 103 feet  
Surface pipe 10 3/4 Inch @ 1136 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Co Tools License# \_\_\_\_\_

Address: \_\_\_\_\_

Company to plug at: Hour: 11:30 A.M. Day: 16 Month: December Year: 1996

Plugging proposal received from: Charlie Farr

Company: Consultant Phone: \_\_\_\_\_

Were: Order 300 sxs 60/40 posmix - 10% gel - hulls - 20 sxs gel.

12-23-96

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]


Completed: Hour: 1:30 P.M., Day: 16, Month: December, Year: 1996

Actual plugging report: 16" to 103'. 10 3/4" to 1136'. 7" to 3443'. Remove casing hanger and orange peel 10 3/4" to 7" casing with collar. Tied onto 7" casing and pumped 75 sxs cement with 500# hulls, 20 sxs gel and 225 sxs cement. Max. P.S.I. 500#. S.I.P. 200#. Tied onto annulus with instant 500# S.I.P.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC X, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: 1921 GL

I did [ ] / did not [ X ] observe the plugging.

  
(agent)  
DH

DATE: JAN 03 1997  
NO. 47230