

J
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Stamp: MAR 28 1966 03-28-66

Operator's Full Name Frank J Black

Complete Address: Box 150 McPherson, Kansas

Lease Name J Johanson Well No. 6

Location NW SE NE Sec. 22 Twp. 11 Rge. 17 (E) (W)

County Ellis Total Depth 3407

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 12 P Day 26 Month 3 Year 1966

The Above well was plugged as follows:

Total Depth-3407 16" set at 50' 10 3/4 set at 1165' cwc 7" set at 3401 (cw200sc)

Sand to 3375' and dumped 5 sax cement with dump bailer

Bridge Plug- 10' Rock- 40 SAX cement At 480' - Dry mud w/ 10 sax Bel to 40' Built solid bridge - left Rock- 10 sax cement to base of Cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2.28.66
INV. NO. 2938-W

Signed: Leo Murray
Well Plugging Supervisor