

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 6-7 County: Ellis

Location: SE SE SE Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3381

I have this date completed supervision of plugging of:

Lease Name: Johansen Well No. 7

Operator's Full Name: Sohio Oil Co

Complete Address: Box 673 Russell, Kans

Plugging Contractor: West Supply Co

Address: Chase Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 19 Month 1 Year 59

The above well was plugged as follows:

16" at 28' - 10 3/4" 1115' circulated with cement - 7" 3375' with 150
sax cement.

Filled with sand to 3360', set 5 sax cement with dump bailer, pulled
2017' 7" to 500', circulated hole with heavy mud through 7" at 500',
displaced 30 sax cement through 7" at 400', heavy mud to 180', displaced
30 sax cement through 7" - heavy mud to 30', set rock and 10 sax cement
to bottom cellar.

Mudding and cementing by West Supply Co's pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 22T 11 R 17W
BOOK PAGE 6 LINE 7

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1959
01-29-59
CONSERVATION DIVISION
Wichita, Kansas