

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 6-6 County: Ellis
Location: NW SE SE Sec. 22 Twp. 11 Rge. 17 (E) (W)
Name of Field: _____ Total Depth: 3387

I have this date completed supervision of plugging of:

Lease Name: Johansen Well No. 6
Operator's Full Name: Sohio Oil Co
Complete Address: Box 673 Russell, Kans
Plugging Contractor: West Supply Co
Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 31 Month 1 Year 59

The above well was plugged as follows:

15" at 35' - 10 3/4" 1121' circulated with cement - 7" 3380' with
150 sax cement behind, squeezed with cement at approx. 2500'.
Filled with sand to 3370', set 5 sax cement with dump bailer, pulled
1520' 7" to 500', circulated hole with heavy mud (Gel) through 7"
at 500', displaced 30 sax cement through 7" at 450', heavy mud to 180',
displaced 30 sax cement through 7" at 180', heavy mud to 50', set rock
and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co's pump truck!

Signed: *Jewel M. Ogden*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 22 T. 11 R. 17
BOOK PAGE 6 LINE 6

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1959
CONSERVATION DIVISION
Wichita, Kansas
02-04-59