

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 28 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Sohio Oil Co

Complete Address: Box 575 Russell, Kansas

Lease Name Johansen Well No. 5

Location SW SE SE Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 5395

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 430

Operation Completed: Hour 1PM Day 23 Month 9 Year 64

The Above well was plugged as follows:

15" 50' - 10 3/4" 1134' circulated with 325 sax cement - 7" 5589' with 150 sax cement. 3" tubing lost in hole - top of tubing at 2757'

Pulled 7" to 985' - circulated hole with heavy gel mud through 7" (32 sax Gel) - pulled 7" to 450' - displaced 25 sax cement through 7" at 450', heavy mud to 200', displaced 25 sax cement through 7" at 200', Heavy mud to 35', set bridge and filled to bottom cellar with cement

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
DATE 9/28/64  
INV. NO. 9882-14

Signed: Edwin Perry  
Well Plugging Supervisor