

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

09-18-64

Operator's Full Name Sohio Oil Co

Complete Address: Box 675 Russell, Kans

Lease Name Johansen Well No. 4

Location NE SW ^{SE} ~~NE~~ Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3416

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 4PM Day 15 Month 9 Year 64

The Above well was plugged as follows:

15" 30' - 10 3/4" 1146' circulated with cement - 7" 3416' with 150 sax cement tubing lost in hole - top of tubing at 3351' - set plug at 3351' sand to 3340' - set 5 sax cement with dump bailer.

Pulled 2408' 7" to 1090' - circulated hole with heavy gel mud through 7" at 1090' - 37 sax gel) - displaced 30 sax cement through 7" at 450' - heavy mud to 240' - displaced 30 sax cement through 7" at 240' - heavy mud to 30', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 9/18/64
INV. NO. 9829-u

Signed: Eddon Perry
Well Plugging Supervisor