

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

11-03-60

File No. \_\_\_\_\_ County: ~~Ellis~~ Ellis

Location: SW NE S3 Sec. 21 Twp. 11 Rge. 17 (E) (W)

Name of Field: Bemis Total Depth: 5456

I have this date completed supervision of plugging of:

Lease Name: J. Johansen PNB vcc Well No. 1

Operator's Full Name: Socony Mobil Oil

Complete Address: 500 N Broadway Wichita, Kansas

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11AM Day 1 Month 11 Year 60

The above well was plugged as follows:

16" 55' circulated with cement - 10 3/4" 1208' circulated with 525 sax cement - 7" 5451' with 200 sax cement.

Filled with sand to 5420', set 5 sax cement with dump trailer, pulled 2219' 7' to 520', circulated hole with heavy mud through 7" at 520'.

Ø 50 sax Gel), displaced 50 sax cement through 7' at 520', heavy mud to 160', displaced 50 sax cement through 7" at 160', heavy mud to 55', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

11-03-60  
11/23/60  
2/7/61