

15-051-05997-0001

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Ormand Industries, Inc.

Complete Address 12011 San Vicente Blvd., Los Angeles, California 90049

Lease Name Bemis "A" Well No. 3

Location NE NW NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3480'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour        Day 11<sup>th</sup> Month 7 Year 1973

The above well was plugged as follows:

Total Depth 3480' 15 1/2" csg set at 52' cwc 10 3/4" csg set at 1104' cwc 325 sk.

7" csg set at 3408' cw 125 sk cem.

5 1/2" csg liner set from (3383'-3480')

Set plug at 3415'-poured 10' sand -Dumped 5 sk cem. W/dump bailer. (3385-3415)

Cutoff and recovered 1997' of 7" csg.

Filled 7" csg to 365'- set rock & sand bridge (350-365)

Dumped 7 yds readymix cmt from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 7/13/73  
INV. NO. 7624-11