

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 14-59 County: Ellis

Location: NE NE SW Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 5505

I have this date completed supervision of plugging of:

Lease Name: Bemis Well No. C-8

Operator's Full Name: Sohio Oil Co

Complete Address: Box 673 Russell, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 20 Month 2 Year 59

The above well was plugged as follows:

15" at 33' - 10" 1175' circulated with cement - 7" 3445' with 150
sax cement behind - 5 1/4" liner 143' top liner 5500'.

Filled with sand to 3450', set 5 sax cement with dump bailer, pulled
2400' 7" to 500', circulated hole with heavy mud through 7" and
displaced 50 sax cement through 7" at 500', heavy mud to 180',
displaced 50 sax cement through 7" at 180', heavy mud to 30', set
rock and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co pump truck.

Signed: *Edon Letty*
Conservation Division Agent

Reviewed: *J Lewis Brock*
Field Supervisor

STATE CORPORATION COMMISSION

Remarks:

PLUGGING
FILE SEC. 22 T. 11 R. 100
BOOK PAGE 14 LINE 39

MAR 5 1959
03-05-59
CONSERVATION DIVISION
Wichita, Kansas