

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 147-10

LOCATION S7 S11 S17

SEC. 22 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 4 Lease F.A. Bemis AUBKCC

Operator Toland & Reeves Address c/o Forbes Casing Pulling Co
Great Bend, Kans

Field _____ County Ellis

Total Depth 3476 Feet.

Plugging Contractor Forbes Casing Pulling Co

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

10" at 142' circulated with cement - 10 3/4" 1200', circulated with 525
sax cement - 7" 5453' with 180 sax cement behind.

Filled with sand to 3440', set 5 sax cement with dump bailer.

pulled no pipe - found it squeezed and circulated to 0'. Shot pipe

at 5250', pumped hole full heavy commercial mud (50 sax gel), pumped

cementing plug to 500', followed by 100 sax cement - cement 500' to 0'.

Edwin Petty
District Conservation Agent

Date 5-25-57

PLUGGED
FILE SEC. 22 11 17W
BOOK PAGE 147 12

MAY 28 1957
05-28-57
CONSERVATION DIVISION
WICHITA, KANSAS