

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1959
CONSERVATION DIVISION
WICHITA, KANSAS

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 14-57 County: Ellis

Location: NE SE SW Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 5497

I have this date completed supervision of plugging of:

Lease Name: Bemis Well No. C-6

Operator's Full Name: Sohio Oil Co

Complete Address: Box 675 Russell, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 7 Month 3 Year 59

The above well was plugged as follows:

15' at 29' - 10 3/4" 1227' circulated with cement - 7" 5489' with 200 sax
cement behind.

Filled with sand to 5470', set 5 sax cement with dump bailer, pulled
2515' 7" to 550' circulated hole with heavy mud (Gel) through 7" at
550', displaced 50 sax cement through 7" at 550', heavy mud to 180',
displaced 50 sax cement through 7" at 180', heavy mud to 30', set rock
and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co pump truck

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC 22 T. 11 R 17W
BOOK PAGE 14 LINE 37