

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 103-23

LOCATION S3 SE SW

SEC. 22 TWP. 11 RGE. 17

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. C-5 Lease Bemis

Operator Sohio Oil Co Address Box 673 Russell, Kans

Field County Ellis

Total Depth 3462 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address

(Describe briefly the manner in which the well was plugged)

16" at 37' - 10" at 1202' circulated with cement - 7" at 3460'
with 200 sax cement behind.

Filled with sand to 3440', set 5 sax cement with dump bailer,
pulled 1778' 7" - filled hole with Gel mud to 300', set rock
and 30 sax cement - Gel mud to 45', set rock and 20 sax cement
to bottom cellar.

PLUGGING
FILE SEC 22 T. 11 R. 17 W.
BOOK PAGE 123 L. E. 22

01-10-57
CONSERVATION
DIVISION

Edwin Kelley
District Conservation Agent
Date 1-2-57