

15-051-05831-0000

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 14-55 County: Ellis

Location: NW SE SW Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 5478

I have this date completed supervision of plugging of:

Lease Name: Bemis Well No. C-5

Operator's Full Name: Sohio Oil Co

Complete Address: Box 675 Russell, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 10 Month 5 Year 59

The above well was plugged as follows:

15" at 55' - 10 3/4" 1215' circulated with 550 sax cement - 7" 5470' with 200 sax cement behind.

Filled with sand to 5460', set 5 sax cement with dump bailer, pulled 2608' 7" to 550', circulated hole with heavy mud through 7" (55 sax Gel), displaced 50 sax cement through 7" at 550', heavy mud to 180', displaced 30 sax cement through 7" at 180', heavy mud to 50', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co's pump truck .

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC 22 T. 11 R. 17w
BOOK PAGE 14 LINE 35

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1959

CONSERVATION DIVISION
WICHITA, KANSAS