

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 14-34 County: Ellis

Location: SW NE SW Sec. 22 Twp. 11 Rge. 17 (E) (W)

Name of Field: Bemis Total Depth: 3515

I have this date completed supervision of plugging of:

Lease Name: Bemis Well No. G-2

Operator's Full Name: Sohio Oil Co

Complete Address: Box ~~xxx~~ 073 Russell, Kans

Plugging Contractor: West Suplly Co

Address: Chase, Kans License No. 14

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes No

If yes how long? _____ Reason: _____

Operation Completed: Hour 9:30AM Day 20 Month 2 Year 59

The above well was plugged as follows:

15" at 58' circulated with cement - 10" 1195' circulated with cement,

7" 3458' with 150 sax cement behind. 5 1/2" liner 3504' to 3515'.

Filled with sand to 3500', set 5 sax cement with dump bailer.

pulled 2415' 7" to 550', circulated hole with heavy mud through 7"

at 550' (Gel mud), displaced 30 sax cement through 7" at 550',

heavy mud to 180', displaced 30 sax cement through 7" at 180', heavy

mud to 30', set rock and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co's pump truck.

Signed: *Edwin Perry*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

MAR 5 1959
03-05-59
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 22 T. 11 R. 17W
BOOK PAGE 14 LINE 34