

15-051-05829-0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1962
09-14-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sohio Oil Co
Complete Address: Box 673 Russell, Kansas
Lease Name Bemis Well No. C-1
Location NW NE SW Sec. 22 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3450
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kans License No. 436
Operation Completed: Hour 4PM Day 12 Month 9 Year 62

The Above well was plugged as follows:

15" 99' circulated with cement 10" 1159' circulated with cement - 7" 3445'
with 150 sax cement.

Sand back to 3435', set 5 sax cement with dump bailer, pulled 2625' 7" -
filled hole with heavy gel mud to 450', set 20 sax cement at 450', heavy mud to
180', set 20 sax cement at 180', heavy mud to 30', set bridge and 10 sax cement
to bottom cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/14/62
INV. NO. 5693-u

Signed: [Signature]
Well Plugging Supervisor