

15-051-05039-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT
STATE CORPORATION COMMISSION

RECEIVED
APR 20 1973
04-20-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ormand Industries, Inc.

Complete Address 12011 San Vincente Blvd., Los Angeles, California 90049

Lease Name Bemis "B" Well No. 8 B

Location C N/2 SW NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3490'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated ~~XXXXXXXXXXXXXXXX~~

Plugging Contractor Kelsay Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 A Day 18 Month 4 Year 1973

The above well was plugged as follows:

Total Depth 3490' 8 5/8 csg set at 1095' cwc 550 sk.

5 1/2 csg set at 3489' cw 350 sk cmt.

5 1/2 csg squeezed at 2216' W/300 sk cmt. Top of cem. 1598'.

Set rock & sand bridge at 1760' -Dumped 5 sk cmt W/dump bailer.

Cutoff and recovered 1564' of 5 1/2 csg.

Set 8 5/8 plug at 435' -rock & sand bridge (375'-435')

Dumped 6 yds readymix cmt from 375' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Moseley
Well Plugging Supervisor

INDEXED
4/23/73
7265-W