

15-051-05853-0001

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1973
D6-11-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ormand Industries, Inc.
Complete Address 12011 San Vicente Blvd., Los Angeles, California 90049
Lease Name Bemis "B" Well No. 7B BMB KCI
Location C N/2 S/2 NW Sec. 22 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3446'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling
Address Box 176 Chase, Kansas 67524 License No. 683
Operation Completed: Hour 12 N Day 6 Month 6 Year 1973

The above well was plugged as follows:

Total Depth 3446' 9 7/8 csg set at 1200' cwc 325 sax.

5 1/2 csg set at 3415' cw 100 sk cmt.

2 stage collar st & circ W/cem 350' sax. No pipe recovered.

Hole plugged at 1400' -set wood plug & dumped 5 sk cmt W/dump bailer.

Filled 5 1/2 csg W/mud to 420' -set rock & sand bridge (410-420)

Filled with readymix cem. from 410' to base of cellar.

Checked anulus -Okay.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Mearns
Well Plugging Supervisor

INVOICED

DATE 6/12/73
INV. NO. 7481-W