

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1969
CONSERVATION DIVISION
Wichita, Kansas

04-28-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ormand Industries, Inc.

Complete Address: 2118 Adolphus Tower Dallas, Texas 75202

Lease Name Bemis "B" Well No. 6

Location NE SE NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3474

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: night Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5:45P Day 25 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 3474' 10 3/4 csg set at 1048' cwc 325 sk

7" csg set at 3435' cw 300 sk cmt.

Filled 7" csg W/sd (3425-3474) Dumped 7 sk cmt W/dump bailer. (3385-3425)

Shutoff and recovered 2375' of 7" csg.

Pumped down 10 3/4 csg with 30 sk gel W/5 sk hulls and 160 sk 50-50 poz cmt W/6% total gel. Max. pres. 900 lbs. SI pres. 900 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Massey
Well Plugging Supervisor

APPROVED
4/28/69
WV. NO. 9654-U