

15-051-05851-0000

Form CP-3
Rev. 6-4-68

KANSAS

78
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUL 2 1973
07-02-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Ormand Industries, Inc.
Complete Address 12011 San Vicente Blvd., Los Angeles, California 90049
Lease Name Bemis "B" Well No. 5B *DUE REC*
Location SE SE NW Sec. 22 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3457' 3444 *AKS REC*
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Pipe Pulling
Address Box 176 Chase, Kansas 67524 License No. 683
Operation Completed: Hour 11 A Day 30 Month 6 Year 1973

The above well was plugged as follows:

Total Depth 3457' 16" csg 32' cw 30 sx. 10 3/4 csg 1152' cwc 338'sx.

7" csg set at 3437' cw 125 sk.

Filled 7" csg W/sd (3420-3457) Dumped 5 sk cmt W/dump bailer. (3400-3420)

Cutoff and recovered 1800' of 7" csg.

Filled 10 3/4 csg with mud to 425' -set rock & sand bridge (410-425)

Dumped 7 1/2 yds readymix cmt from 410' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

RECORDED

Signed: *Geo J. Truesdell*
Well Plugging Supervisor

DATE 7/2/73
INV. NO. 7584-W