

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1973
06-11-73
CONSERVATION DIVISION
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ormand Industries, Inc.

Complete Address 12011 San Vicente Blvd. Los Angeles, California 90049

Lease Name Bemis "B" Well No. 4

Location SW SE NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3457'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 4:30 P Day 7 Month 6 Year 1973

The above well was plugged as follows:

Total Depth 3457' 10 3/4 csg set at 1131' cwc 325 sk. 15" csg 36' cwc 40 sk.

7" csg set at 3414' cw 125 sk.

5 1/2" liner set (2605-3444) cemented. Perf. (3414-3420)

7" csg squeezed at 1909' W/300 sx cem.

Filled 5" liner W/sd (3400-3457) dumped 5 sk cmt W/dump bailer. (3365-3400)

Cutoff and recovered 1515' of 7" csg.

Mud to 370' -set rock & sand bridge (350-370)

Dumped 6 yds readymix cem. from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Eric P. Massey
Well Plugging Supervisor

INVOICED

DATE 6/12/73
INV. NO. 7480-W