

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ormand Industries, Inc.

Complete Address 12011 San Vicente Blvd., Los Angeles, California 90049

Lease Name Bemis "B" Well No. 2

Location SW SW NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3414'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:15 P Day 26 Month 6 Year 1973

The above well was plugged as follows:

Total Depth 3414' 16" csg 37' cw 35 sx. 10" csg 1093' cw: 300 sx.

7" csg 3372' cw 135 sx. cem.

Lane Wells steel plug set at 3395' cw 1 sx Cal-Seal cem.

5" csg liner (3350-3408)

7" csg squeezed from (2301'-2750')

Set 7" wood plug at 2832' -poured sand (2800'-2832') Dumped 5 sx cem. W/dump bailer.

Cutoff and recovered 700' of 7" csg.

Mud to 380' -set rock & sand bridge (350-380') Dumped 6 1/2 yds readymix cem. 350-base of

cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 6/28/73

INV. NO. 7560-u